



**Tender form & BOQs for Accessibility/Modification of Health Facilities at
Khanewal,Punjab,Pakistan**

Tender#PIEH Khanewal (CHIP-SS)-2023-011(01)

1. BOQ for Accessibility/Modification OF DHQ Hospital , Khanewal

S no	Item	Description	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" lunge Rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	46		
2	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2 " with fixing and fitting complete in all respects size 3.5 x7' (Plastic)	Sft	24.5		
3	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1;2;4) complete in all respects.(Iron)	No	1		
4	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet, with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						

2. BOQ for Accessibility/Modification OF LRBT Hospital,Khanewal

S no	Item	Description	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	40		
2	Sand	Sand(River sand)	Cft	220		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	200		
4	Bricks	Bricks(1st Class)	Nos	210		
5	Removing	Removing of WC and Wash hand basin.	No	2		
6	Dismantling	Dismantling of brick work lime or cement mortar.	Cft	13.78		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	51.25		
8	Removing	Removing of door with chowkat	No	1		
9	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	502		
10	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long Rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	10		
11	Glazed tile	Providing and laying glazed tile size (20"*10") or (16"*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom.(local)	Sft	86.25		
12	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	149		
13	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2 " with fixing and fitting complete in all respects size 3.5 x7' (Plastic)	Sft	24.5		
14	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
15	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
16	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	2		
17	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
18	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
19	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	20		
20	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
21	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
22	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
23	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
24	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
25	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quality)	No	1		
26	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,connectin,themble including and connecting with P trap complete in all respects white color (local)	No	1		
27	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				
		25 mm i.d	Rft.	15		
		32mm I. d	Rft.	15		
28	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia, including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		

	(25 mm) Elboww	(25 mm) Elboww	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
	(32mm) Elbowwv	(32mm) Elbowwv	Nos	2		
Electric work						
29	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
30	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
31	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
32	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
33	Exhaust fan	Supply and fixing of exhaust fan (1*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
34	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
35	Pvc board	Supply and erection pvc board size 6"x4" with switch button complete in all respects.(Plastic)	No	1		
36	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
37	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet, with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
3. BOQ for Accessibility/Modification OF RHC Abdul Hakeem ,Khanewal						
S no	Item	Description	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	28		
2	Sand	Sand(River sand)	Cft	80		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	135		
4	Bricks	Bricks(1st Class)	Nos	240		
5	Filling	Earth filling (local mix sand)	Trolley	0.5		
6	Dismantling	Dismantling of cement concrete(1:2:4)	Cft	80.03		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	32.5		
8	Removing	Removing of door with chowkat	No	1		
9	Dismantling	Dismantling of brick work cement or lime mortar.	Cft	4.88		
10	Removing	Removing of WC and old commode set etc.	No	1		
11	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	140		
12	Brick Stone	Providing and laying brick stone ballast 1 1/2" to 2" in foundation and plinth mixed with 25% sand levelling and compaction complete.	Cft	78.21		
13	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	36		
14	Glazed tile	Providing and laying glazed tile size (20*10") or (16*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom,(local)	Sft	32.5		
15	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	164.5		
16	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2" with fixing and fitting complete in all respects size 3.5 x6' (Plastic)	Sft	21		
17	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
18	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
19	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	2		
20	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
21	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
22	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	10		
23	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
24	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
25	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
26	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
27	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
28	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quality)	No	1		
29	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,conectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		
30	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				
		25 mm i.d	Rft.	10		
		32mm I. d	Rft.	10		

31	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		
	(25 mm) Elbow	(25 mm) Elbow	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
	(32mm) Elbow	(32mm) Elbow	Nos	2		
Electric work						
32	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
33	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
34	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
35	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
36	Exhaust fan	Supply and fixing of exhaust fan (1*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
37	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
38	Pvc board	Supply and erection pvc board size 6"x4" with switch button complete in all respects.(Plastic)	No	1		
39	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
40	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
4. BOQ for Accessibility/Modification OF RHC Haveli Koranga ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	13		
2	Sand	Sand(River sand)	Cft	50		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	60		
4	Bricks	Bricks(1st Class)	Nos	80		
5	Removing	Removing of cement plaster	Sft	146.24		
6	Marble Chips	1 1/2 "thick mosaic flooring, consisting of 12" thick mosaiaic topping of one part of cement and marble powder in the ratio of 3:1 and two part of marble chips laid over 1" thick of cement concrete(1:2:4) including rubbing and polishing complete with finishing.	Sft	15.38		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	156		
8	Removing	Removing of door with chowkat	No	1		
9	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	140		
10	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3"each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	32		
11	Glazed tile	Providing and laying glazed tile size (20"*10") or (16"*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom,(local)	Sft	132.5		
12	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	179		
13	Door	Providing and fixing plastic made door with plastic frame 4"x 1 1/2 " with fixing and fitting complete in all respects size 3.5 x6' (Plastic)	Sft	21		
14	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
15	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
16	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	2		
17	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
18	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
19	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	10		
20	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
21	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
22	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
23	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
24	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
25	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quality)	No	1		
26	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,connectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		

27	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				
		25 mm i.d	Rft.	15		
		32mm I. d	Rft.	15		
28	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
		(25 mm) Tee	(25 mm) Tee	Nos	3	
		(25 mm) socket	(25 mm) socket	Nos	3	
		(25 mm) union	(25 mm) union	Nos	3	
		(25 mm) Elbow	(25 mm) Elbow	Nos	3	
		(32 mm) Tee	(32 mm) Tee	Nos	2	
		(32 mm) socket	(32 mm) socket	Nos	2	
		(32mm) union	(32mm) union	Nos	2	
		(32mm) Elbow	Nos	2		
Electric work						
29	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
30	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
31	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
32	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
33	Exhaust fan	Supply and fixing of exhaust fan (1*1) size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
34	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
35	Pvc board	Supply and erection pvc board zize 6"x4" with switch button complete in all respects.(Plastic)	No	1		
36	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
37	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
5. BOQ for Accessibility/Modification OF RHC Katcha Khuh ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	20		
2	Sand	Sand(River sand)	Cft	60		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	90		
4	Bricks	Bricks(1st Class)	Nos	308		
5	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	192		
6	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	20		
7	Glazed tile	Providing and laying glazed tile size (20"*10") or (16"*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom.(local)	Sft	130		
8	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	42.5		
9	Door	Providing and fixing plastic made door with plastic frame 4"x 1 1/2 " with fixing and fitting complete in all respects size 3.5 x6' (Plastic)	Sft	21		
10	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
11	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
12	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	2		
13	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
14	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
15	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	10		
16	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
17	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
18	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
19	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
20	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
21	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quailty)	No	1		
22	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,connectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		
23	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				

		25 mm i.d	Rft.	15		
		32mm I. d	Rft.	15		
24	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		
	(25 mm) Elbow	(25 mm) Elbow	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
		(32mm) Elbow	(32mm) Elbow	Nos	2	
Electric work						
25	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	30		
26	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
27	PVC strip pattii	Supply and erection of PVC strip pattii for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
28	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
29	Exhaust fan	Supply and fixing of exhaust fan (1*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
30	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
31	Pvc board	Supply and erection pvc board size 6"x4" with switch button complete in all respects.(Plastic)	No	1		
32	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2;4) complete in all respects.(Iron)	No	1		
33	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
6. BOQ for Accessibility/Modification OF RHC Kukkar Hutta ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	1		
2	Sand	Sand(River sand)	Cft	10		
3	Removing	Removing of cement plaster	Sft	64		
4	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	36		
5	Removing	Removing of door with chowkat	No	1		
6	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	17.5		
		Hand railing for ramp fixed on wall 2" dia stainless steel pipe 16 SWG complete in all respects(SS)	Rft	17.5		
7	Glazed tile	Providing and laying glazed tile size (20"*10") or (16"*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom,(local)	Sft	36		
8	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	137		
9	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2 " with fixing and fitting complete in all respects size 3.5 x6' (Plastic)	Sft	21		
10	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/ 2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
11	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
12	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	2		
13	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
14	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
15	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	10		
16	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
17	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
18	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
19	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
20	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
21	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quality)	No	1		
22	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,conectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		
23	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				
		25 mm i.d	Rft.	15		
		32mm I. d	Rft.	15		

24	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		
	(25 mm) Elbow	(25 mm) Elbow	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
	(32mm) Elbow	(32mm) Elbow	Nos	2		
Electric work						
25	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
26	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
27	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
28	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
29	Exhaust fan	Supply and fixing of exhaust fan (1*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
30	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
31	Pvc board	Supply and erection pvc board size 6"x4" with switch button complete in all respects.(Plastic)	No	1		
32	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
33	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
7. BOQ for Accessibility/Modification OF RHC Makhdoom Pur ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	22		
2	Sand	Sand(River sand)	Cft	65		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	115		
4	Bricks	Bricks(1st Class)	Nos	100		
5	Filling	Earth filling (local mix sand)	Trolley	0.5		
6	Dismantling	Dismantling of cement concrete(1:2:4)	Cft	66.55		
7	Dismantling	Dismantling of brick work cement or lime mortar .	Cft	2.81		
8	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	39		
9	Brick Stone	Providing and laying brick stone bllsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand levling and compaction complete.	Cft	55.44		
10	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	140		
11	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	24		
		Hand railing for ramp fixed on wall 2" dia stainless steel pipe 16 SWG complete in all respects(SS)	Rft	24		
12	Glazed tile	Providing and laying glazed tile size (20*10") or (16*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom.(local)	Sft	39		
13	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	179.38		
14	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
15	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
16	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	2		
17	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
18	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
19	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	20		
20	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
21	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
22	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
23	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
24	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
25	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quaity)	No	1		
26	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,conectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		

27	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				
		25 mm i.d	Rft.	20		
		32mm I. d	Rft.	20		
28	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
		(25 mm) Tee	(25 mm) Tee	Nos	3	
		(25 mm) socket	(25 mm) socket	Nos	3	
		(25 mm) union	(25 mm) union	Nos	3	
		(25 mm) Elbow	(25 mm) Elbow	Nos	3	
		(32 mm) Tee	(32 mm) Tee	Nos	2	
		(32 mm) socket	(32 mm) socket	Nos	2	
		(32mm) union	(32mm) union	Nos	2	
		(32mm) Elbow	Nos	2		
Electric work						
29	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
30	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
31	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
32	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
33	Exhaust fan	Supply and fixing of exhaust fan (1*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
34	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
35	Pvc board	Supply and erection pvc board zize 6"x4" with switch button complete in all respects.(Plastic)	No	1		
36	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
37	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						

8. BOQ for Accessibility/Modification OF RHC Saraey Sidhu ,Khanewal

S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	5		
2	Sand	Sand(River sand)	Cft	50		
3	Crush	Crush (3/8" and1/2" mix)	Cft	20		
4	Bricks	Bricks(1st Class)	Nos	50		
5	Removing	Removing of cement plaster	Sft	7.92		
6	Brick Stone	Providing and laying brick stone bllsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand levling and compaction complete.	Cft	84.48		
7	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	12		
		Hand railing for ramp fixed on wall 2" dia stainless steel pipe 16 SWG complete in all respects(SS)	Rft	12		
8	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
9	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						

9. BOQ for Accessibility/Modification OF RHC Sardar Pur ,Khanewal

S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	18		
2	Sand	Sand(River sand)	Cft	60		
3	Crush	Crush (3/8" and1/2" mix)	Cft	90		
4	Bricks	Bricks(1st Class)	Nos	170		
5	Brick Stone	Providing and laying brick stone bllsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand levling and compaction complete.	Cft	112.68		
6	Dismantling	Dismantling of brick soling and pcc (1:2:4)for walk way and ramp	Cft	168.76		
7	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	140		
8	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	48		
		Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
10	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
11	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		

12	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
13	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
14	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
15	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quality)	No	1		
Electric work						
16	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
17	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
18	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
19	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
20	Exhaust fan	Supply and fixing of exhaust fan (1'*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
21	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
22	Pvc board	Supply and erection pvc board size 6"x4" with switch button complete in all respects.(Plastic)	No	1		
23	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
24	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
10. BOQ for Accessibility/Modification OF RHC Tulamba ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	22		
2	Sand	Sand(River sand)	Cft	65		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	100		
4	Bricks	Bricks(1st Class)	Nos	385		
5	Filling	Earth filling (local mix sand)	Trolley	1		
6	Removing	Removing of WC,P trap etc.	No	1		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	36		
8	Removing	Removing of door with chowkat	No	1		
9	Dismantling	Dismantling of cement concrete(1:2:4)	Cft	129.36		
10	Dismantling	Dismantling of brick work lime or cement mortar	Cft	2.44		
11	Brick Stone	Providing and laying brick stone blsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand levling and compaction complete.	Cft	240.24		
12	Railing 2" dia	Hand railing for ramp fixed on wall 2" dia stainless steel pipe 16 SWG complete in all respects(SS) Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	14		
13	Glazed tile	Providing and laying glazed tile size (20"*10") or (16"*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom,(local)	Sft	36		
14	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	79.63		
15	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2" with fixing and fitting complete in all respects size 3.5 x6' (Plastic)	Sft	21		
16	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
	Manhole Cover	Manhole cover with angle iron frame 2' dia front of main intruss	No	1		
Sanitary and plumbing work						
17	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
18	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	2		
19	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
20	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
21	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	10		
22	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
23	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
24	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
25	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
26	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
27	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quality)	No	1		
28	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,conectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		
29	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				
		25 mm i.d	Rft.	10		
		32mm I. d	Rft.	10		

30	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		
	(25 mm) Elbow	(25 mm) Elbow	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
	(32mm) Elbow	(32mm) Elbow	Nos	2		
Electric work						
31	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring ,(Pakistan Cable)	Rft.	20		
32	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring ,(Pakistan Cable)	Rft.	20		
33	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
34	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
35	Exhaust fan	Supply and fixing of exhaust fan (1*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
36	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
37	Pvc board	Supply and erection pvc board size 6"x4" with switch button complete in all respects.(Plastic)	No	1		
38	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
39	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
11. BOQ for Accessibility/Modification OF RHC Thatha Sadiqabad ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	26		
2	Sand	Sand(River sand)	Cft	80		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	125		
4	Bricks	Bricks(1st Class)	Nos	385		
5	Dismantling	Dismantling brick work in lime or cement mortar or cement concrete etc.	Sft	129.88		
6	Removing	Removing of old WC	No	1		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	30		
8	Removing	Removing of door with chowkat	No	2		
9	Brick Stone	Providing and laying brick stone bllsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand leveling and compaction complete.	Cft	137.28		
10	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	140		
11	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	44		
12	Glazed tile	Providing and laying glazed tile size (20*10") or (16*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom.(local)	Sft	72.5		
13	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	99		
14	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2" with fixing and fitting complete in all respects size 3.5 x6' (Plastic)	Sft	50.75		
15	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
16	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
17	P trap	Providing and fixing 4"dia P trap free from any leakage ,(local)	Nos	2		
18	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
19	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
20	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	20		
21	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
22	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
23	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
24	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
25	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
26	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quailty)	No	1		
27	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,conectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		
28	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				

		25 mm i.d	Rft.	10		
		32mm I. d	Rft.	10		
29	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		
	(25 mm) Elbow	(25 mm) Elbow	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
		(32mm) Elbow	(32mm) Elbow	Nos	2	
Electric work						
30	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
31	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
32	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
33	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
34	Exhaust fan	Supply and fixing of exhaust fan (1*1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
35	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
36	Pvc board	Supply and erection pvc board size 6"x4" with switch button complete in all respects.(Plastic)	No	1		
37	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
38	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
12. BOQ for Accessibility/Modification OF THQ Jahania ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	8		
2	Sand	Sand(River sand)	Cft	30		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	32		
4	Bricks	Bricks(1st Class)	Nos	170		
5	Dismantling	Dismantling brick work in lime or cement mortar	Sft	6.38		
6	Removing	Removing of old commode,WC and Wash hand basin.complete set.	No	1		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	81		
8	Removing	Removing of door with chowkat	No	1		
9	Brick Stone	Providing and laying brick stone bllsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand levling and compaction complete.	Cft	35.89		
10	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3'each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects .(Stainless steel)	Rft	29		
11	Glazed tile	Providing and laying glazed tile size (20*10") or (16*10")1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material.wshroom,(local)	Sft	81		
12	Emulsion pain	White wash 2 coat emulsion paint.(Brito/Primex)	Sft	221.75		
13	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2" with fixing and fitting complete in all respects size 3.5 x8.5'(Plastic)	Sft	29.75		
14	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete(SS)	Rft	10		
Sanitary and plumbing work						
15	wash hand basin	Providing and fitting glazed earthen ware wash hand basin(22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects(Local)	No	1		
16	P trap	Providing and fixing 4"dia P trap free from any leakage .(local)	Nos	3		
17	floor waste	Providing and fixing plastic floor waste complete.(Plastic)	No	1		
18	Muslim Shower	Providing and fixing health faucet(Muslim Shower) Chromium Local brand with all fitting, complete in all respects.(Chromium)	No	1		
19	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia.(Pvc)	Rft	20		
20	Toilet paper holder	Providing and fixing plastic made toilet paper holder.(Plastic)	No	1		
21	Soap dish	Providing and fixing plastic made soap dish.(Plastic)	No	1		
22	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia(Chromium)	Nos	4		
23	Towel rail	Providing and fixing plastic made towel rail.(Plastic)	No	1		
24	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
25	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quailty)	No	1		
26	WC	Providing and fixing glazed earthen ware water closet,combined with foot rest.white color(local)	No	1		
27	Flushing cistern	Providing and fitting glazed earthen ware low down flushing cistern 13.3 liter(3 gallons)capisty,including bracket set copper conection etc complete .white color(local)	No	1		

28	Commode set	Providing and fixing western commode set with cover Local Brand with Tee cock, connect, the mble including and connect with P trap complete in all respects white color (local)	No	1		
29	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects (16 Gauge)				
		25 mm i.d	Rft.	20		
		32mm I. d	Rft.	20		
30	Tee, Socket, Elbow w, Union	Providing and installing ball valves of following nominal dia, including jointing, fitting, testing, complete in all respects to match with following PPR pipe diameters. (PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		
	(25 mm) Elbow	(25 mm) Elbow	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
	(32mm) Elbow	(32mm) Elbow	Nos	2		
Electric work						
31	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring. (Pakistan Cable)	Rft.	20		
32	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring. (Pakistan Cable)	Rft.	20		
33	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete. (PVC)	Rft.	20		
34	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
35	Exhaust fan	Supply and fixing of exhaust fan (1'x1') size complete with shutter Luminar brand complete in all respects (Luminar)	No	1		
36	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
37	Pvc board	Supply and erection pvc board size 6'x4' with switch button complete in all respects. (Plastic)	No	1		
38	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects. (Iron)	No	1		
39	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet, with writing complete in all respects (Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
13. BOQ for Accessibility/Modification OF THQ Kabir wala ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	6		
2	Sand	Sand (River sand)	Cft	30		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	20		
4	Bricks	Bricks (1st Class)	Nos	350		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	31.5		
8	Removing	Removing of door with chowkat	No	1		
9	Brick Stone	Providing and laying brick stone bllsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand levling and compaction complete.	Cft	25.88		
10	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3" each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects. (Stainless steel)	Rft	18		
11	Glazed tile	Providing and laying glazed tile size (20" x 10") or (16" x 10") 1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material. wshroom, (local)	Sft	145.5		
12	Emulsion pain	White wash 2 coat emulsion paint. (Brito/Primex)	Sft	275		
13	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2" with fixing and fitting complete in all respects size 2x3.5 x6.5' (Plastic)	Sft	45.5		
14	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete (SS)	Rft	10		
Sanitary and plumbing work						
15	wash hand basin	Providing and fitting glazed earthen ware wash hand basin (22" x 21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects (Local)	No	1		
16	P trap	Providing and fixing 4" dia P trap free from any leakage. (local)	Nos	2		
17	floor waste	Providing and fixing plastic floor waste complete. (Plastic)	No	1		
18	Muslim Shower	Providing and fixing health faucet (Muslim Shower) Chromium Local brand with all fitting, complete in all respects. (Chromium)	No	1		
19	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia. (Pvc)	Rft	10		
20	Toilet paper holder	Providing and fixing plastic made toilet paper holder. (Plastic)	No	1		
21	Soap dish	Providing and fixing plastic made soap dish. (Plastic)	No	1		
22	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2" dia) (Chromium)	Nos	4		
23	Towel rail	Providing and fixing plastic made towel rail. (Plastic)	No	1		
24	Mirror shelf	Providing and fixing plastic made mirror shelf. (Plastic)	No	1		
25	Looking glass	Providing and fixing looking glass (24" x 18") size, and 5mm thick, first quality with fitting complete. (1st quality)	No	1		

26	Commode set	Providing and fixing western commode set with cover Local Brand with Tee cock, connect, the mble including and connect with P trap complete in all respects white color (local)	No	1		
27	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects (16 Gauge)				
		25 mm i.d	Rft.	10		
		32mm I. d	Rft.	10		
28	Tee, Socket, Elbow w, Union	Providing and installing ball valves of following nominal dia, including jointing, fitting, testing, complete in all respects to match with following PPR pipe diameters. (PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	2		
	(25 mm) socket	(25 mm) socket	Nos	2		
	(25 mm) union	(25 mm) union	Nos	2		
	(25 mm) Elbow	(25 mm) Elbow	Nos	2		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
	(32mm) Elbow	(32mm) Elbow	Nos	2		
Electric work						
29	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring. (Pakistan Cable)	Rft.	20		
30	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring. (Pakistan Cable)	Rft.	20		
31	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete. (PVC)	Rft.	20		
32	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
33	Exhaust fan	Supply and fixing of exhaust fan (1'x1') size complete with shutter Luminar brand complete in all respects (Luminar)	No	1		
34	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
35	Pvc board	Supply and erection pvc board size 6'x4' with switch button complete in all respects. (Plastic)	No	1		
36	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects. (Iron)	No	1		
37	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet, with writing complete in all respects (Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
14. BOQ for Accessibility/Modification OF THQ Mian Channo ,Khanewal						
S no	Item	Discription	Unit	Quantity	Unit Rate	Amount
Civil work						
1	Cement	Cement (Maple leaf/Pioneer) fresh stock	Bags	79		
2	Sand	Sand (River sand)	Cft	203		
3	Crush	Crush (3/8" and 1/2" mix)	Cft	388		
4	Bricks	Bricks (1st Class)	Nos	260		
5	Filling	Earth filling (local mix sand)	Trolley	3		
6	Dismantling	Dismantling of cement concrete (1:2:4) wash room front plate form	Cft	49.34		
7	Dismantling	Dismantling glazed tiles or mosaic flooring chips.	Sft	30		
8	Removing	Removing of door with chowkat	No	1		
9	Marble strip	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels, size 1-1/2"x3/8". (local)	Rft	483.5		
10	Brick Stone	Providing and laying brick stone blsat 1 1/2" to 2" in foundation and plinth mixed with 25% sand levling and compaction complete.	Cft	400.29		
11	Railing 2" dia	Providing and fixing 3' Height hand railing on ramp stainless steel pipe 2" dia top bar and stainless steel pipe 3/4" dia for supporting bar 16 gauge welding with vertical post of 2" dia SS around pipe space 3' each vertical post fixed with 4" long rawal bolt i/c stainless steel welding, polishing complete in all respects. (Stainless steel)	Rft	32		
12	Glazed tile	Providing and laying glazed tile size (20"x10") or (16"x10") 1/4" thick dado jointed and laid over tile bond including finishing and joint filled with mach tile filling material. wshroom. (local)	Sft	30		
13	Emulsion pain	White wash 2 coat emulsion paint. (Brito/Primex)	Sft	115.5		
14	Door	Providing and fixing plastic made door with plastic frame 4'x 1 1/2" with fixing and fitting complete in all respects size 3.5 x6' (Plastic)	Sft	21		
15	Railing 1 1/2" dia	Providing and fixing Grab bar pipe stainless steel 1 1/2" dia complete (SS)	Rft	10		
Sanitary and plumbing work						
16	wash hand basin	Providing and fitting glazed earthen ware wash hand basin (22"x21") including bracket set, waste pipe and waste coupling, etc. - white color Local brand with basin mixer complete in all respects (Local)	No	1		
17	P trap	Providing and fixing 4" dia P trap free from any leakage. (local)	Nos	2		
18	floor waste	Providing and fixing plastic floor waste complete. (Plastic)	No	1		
19	Muslim Shower	Providing and fixing health faucet (Muslim Shower) Chromium Local brand with all fitting, complete in all respects. (Chromium)	No	1		
20	Pvc pipe 4" dia.	Providing and laying pvc pipe 4" dia. (Pvc)	Rft	10		
21	Toilet paper holder	Providing and fixing plastic made toilet paper holder. (Plastic)	No	1		
22	Soap dish	Providing and fixing plastic made soap dish. (Plastic)	No	1		
23	Tee cock	Providing and fixing, chromium plated Tee cock pvc head. (1/2") dia (Chromium)	Nos	4		
24	Towel rail	Providing and fixing plastic made towel rail. (Plastic)	No	1		

25	Mirror shelf	Providing and fixing plastic made mirror shelf.(Plastic)	No	1		
26	Looking glass	Providing and fixing looking glass (24"x18") size, and 5mm thick, first quality with fitting complete.(1st quality)	No	1		
27	Commode set	Providing and fixing western commode set with cover Local Brand with T cock,connectin,themble including and conectin with P trap complete in all respects white color (local)	No	1		
28	PPR pipe	Providing, fixing, jointing and testing Polypropylene Random (PPR) pipe for fittings (polyfusion welded joints) inside building complete in all respects(16 Gauge)				
		25 mm i.d	Rft.	10		
		32mm I. d	Rft.	10		
29	Tee,Socket,Elbow w,Union	Providing and installing ball valves of following nominal dia,including jointing ,fitting, testing, complete in all respects to match with following PPR pipe diameters.(PPR)				
	(25 mm) Tee	(25 mm) Tee	Nos	3		
	(25 mm) socket	(25 mm) socket	Nos	3		
	(25 mm) union	(25 mm) union	Nos	3		
	(25 mm) Elbow	(25 mm) Elbow	Nos	3		
	(32 mm) Tee	(32 mm) Tee	Nos	2		
	(32 mm) socket	(32 mm) socket	Nos	2		
	(32mm) union	(32mm) union	Nos	2		
	(32mm) Elbow	(32mm) Elbow	Nos	2		
Electric work						
30	Cables 3.029	Supply and fixing of single core PVC insulated copper, conductor cables 3.029 for wiring .(Pakistan Cable)	Rft.	20		
31	Cables 7.029	Supply and fixing of single core PVC insulated copper, conductor cables 7.029 for wiring .(Pakistan Cable)	Rft.	20		
32	PVC strip patti	Supply and erection of PVC strip patti for wiring on walls, including bends, inspection joints, boxes, pull boxes, hook complete.(PVC)	Rft.	20		
33	LED Bulb	Supply and erection of LED Bulb 18watts	Nos	2		
34	Exhaust fan	Supply and fixing of exhaust fan (1'x1') size complete with shutter Luminar brand complete in all respects(Luminar)	No	1		
35	Button holder	Supply and erection of button holder brass. (Brass)	Nos	2		
36	Pvc board	Supply and erection pvc board zize 6"x4" with switch button complete in all respects.(Plastic)	No	1		
37	Sign Board	Sign board of iron sheet 18 SWG size 3'x2'x5' with writing and fixed with in 1' cement concrete (1:2:4) complete in all respects.(Iron)	No	1		
38	Sign Board	Sign board plastic sheet size 2'x2' for PWD for placing on the door to be made accessible toilet,with writing complete in all respects(Plastic)	No	1		
Total inclusive of labor/taxes and transportation						
Grand Total inclusive of labor/taxes and transportation						